



218 7th Ave S, Jacksonville Beach Road Construction Project

Estimated Construction
Phase Start Date:
September 2024

Estimated Construction
Phase Completion Date:
March 2025



Phase 3

Phase Information:

This phase involves reconstruction of the existing City roadway and alley right-of-way to bring roadways, sidewalks and driveways to current city standards. New curb inlets will be constructed and piped to the new storm trunk line on 1st St. S. The existing potable water main on the west side of 2nd St. S. from 7th to 5th will also be replaced, as the existing pipeline has reached its end of useful life. All existing water mains on the Avenues within this phase will be replaced. The existing gravity sewers in the alleyways will be removed and replaced. The existing water meter service boxes and electrical boxes will also be replaced throughout project limits. The existing street lighting on 2nd St. S. will be relocated, as necessary, and new conventional street lighting installed on the avenues. The contractor will coordinate with property owners to maintain vehicular and pedestrian access as well as emergency vehicle access within project limits. Oceanfront Park will also be milled and resurfaced during this Phase.

Construction Work Zone Limits:

Encompasses 2nd St. S. from 11th to 10th Ave. S., 8th to 7th Ave. S. and 5th to 4th Ave. S. and also 10th, 7th and 5th Ave. S. from 2nd to 1st St. S. Oceanfront Park will also be milled and resurfaced during this Phase.

Information Obtained From:

<https://www.jacksonvillebeach.org/299/Construction-Projects-Road-Closure-Update>

<https://gai-consultants.maps.arcgis.com/apps/dashboards/b4b8ac134d074f30b31bfd498986306>