



**CUSTER COUNTY PERMIT FOR
INSTALLATION OF ON-SITE
WASTEWATER TREATMENT SYSTEM**

101-80-345
Allan Brain
Christina
103 Yucca Ln
Westcliffe, CO 81252

S21050621

Issue Date: 5/6/2021

Septic Contractor: Myron Mullett Soil done by: Edward Cody Lyons Soil Date: 4/23/2021
Applicant: Owner

Permit Type: Installation System Type: Standard

Property Address: 1115 Eagles Gate Rd

Legal: Lot 30 Eagle Springs Ranch Filing 2

Lot size: 35.85 Number of people: 8 Number of bedrooms: 4 Tank Size: 1250

This septic will serve a Dwelling Water: Private Well

Conditions: Depth to bedrock: >96" Depth to water: >96" Slope:

Soil Type: 2 Treatment Level: 1 Effluent Application Method: Gravity

	Rock or Tire Chips Sq. Ft.	Mfd Media other than Chambers Sq. Ft.	Chambers Sq. Ft.	Number of Chambers
Trench	1000	900	700	58
Bed	1200	1080	840	70

Comments:

I hereby certify that I have installed this system as designed:

Licensed Contractor / Homeowner

5-25-2021
Date

Inspected on: 5/25/2021

By: ESM

Amount use tax paid: _____

Date: _____

W. Kitchman

Final approval date: 5/26/2021

Zoning Office / Inspector

Septic Inspection

Property Owner(s): Allan Brain
Christina

Date: 5-25-2021

Inspected By: JSH

Property Address: 1115 Eagles Gate Rd
Legal: Lot 30 Eagle Springs Ranch Filing 2

Septic Contractor: Myron Mullett

Schedule #: 101-80-345

Permit Number: S21050621

Distance of Pipe from House to Tank: 13'

Distance DBL Cleanouts: No

Number of cleanouts needed (50 feet): No

Check slope (1/2 inch per 2 feet for last 10 feet before tank): OK

Type of pipe (schedule number): S4040

Building Sewer extended to foundation: No

Tank size: 1200 BEM Is tank level?: OK

Check: Inlet OK Outlet OK

Check for cracks in tank: OK Date on tank: 5-10-2021

Distance of pipe from tank to leach field: 52' Check for slope: OK

Check for level distribution field: OK Type of pipe (schedule number) S4040

Type of leach field: Duck 4 Number, if chambers: 18+18+11+170

Check for screws on chamber connections: OK

Configuration: Trench or Bed (Max 12' wide, 4' deep) Check for level: OK

Depth: 2-2 1/2' Check distance between trenches (4 feet minimum):

Distance from well to tank: No (50 feet minimum) Distance from well to leach field: No (100 feet minimum)

Distance from leach field to any irrigation ditch or creek: (Minimums: Cistern - 25'; property line - 10'; water course - 50'; dry gulch - 25')

Additional comments: