



Notes:

1. Approx 530 feet 1.5" PEX-A Piping
2. Approx 250 feet 1/2" PEX-A Piping
3. (42) 1.5" x 1.5" x 1/2" PEX "T" Fittings
4. (4) 1.5" Isolation Valves
5. Approx 20 feet 2" Flexible Potable Water Hose
6. (1) Excess Flow Check Valve
7. Misc Fittings for Connections
8. Access valves to include access holes in concrete decking to be covered by brass covers secured to concrete decking.

Sketch Revision Log

- Rev. 0 - RD Internal DRAFT Only
- Rev. 1 - Issued for Bid Solicitation
- Rev. 2 - Added

- (1) Two additional Isolation Valves
- (2) Access Holes to be drilled or cut into Main Dock Concrete Decking
- (3) Brass Cover Plates to be installed over access holes